

1. DO NOT SCALE DRAWINGS. USE DIMENSIONS SHOWN.
2. SITE DIMENSIONS ARE TO FACE OF CURB, PROPERTY LINE OR FACE OF BUILDING UNLESS OTHERWISE NOTED. ALL DIMENSIONS AND RADII TO OR FROM CURB LINES ARE TO FACE OF CURB.
3. ALL WALKWAY SURFACES SHALL BE BELOW 5% SLOPE, 2% CROSS SLOPE AND SHALL MEET ALL ARCHITECTURAL BARRIERS ACT ACCESSIBILITY STANDARDS AND VA BARRIER FREE DESIGN GUIDE REQUIREMENTS.
4. EXTERIOR FINISH FLOOR FINISH FOR ALL BUILDING FACADE SHALL BE 1/8" MIN., 1/4" MAX. BELOW FINISH FLOOR ELEVATION, TYP.

THESE NOTES PERTAIN TO ALL CONSTRUCTION AND THE FOLLOWING DOCUMENTS

2. ALL UNDERGROUND FACILITIES, STRUCTURES, AND UTILITIES HAVE BEEN PLOTTED FROM THE SURVEY PROVIDED BY THE OWNER. THEREFORE, THE RELATIONSHIP BETWEEN PROPOSED WORK AND EXISTING FACILITIES, STRUCTURES, AND UTILITIES MUST BE CONSIDERED APPROXIMATE. IT IS THE RESPONSIBILITY OF THE CONTRACTOR TO DETERMINE THE EXACT LOCATION AND EXISTENCE OF ANY UTILITIES NOT SHOWN. ALL UTILITIES SHALL BE LOCATED AND MARKED BOTH HORIZONTALLY AND VERTICALLY TO ENSURE CLEARANCE OF ANY PROPOSED SITE WORK. UTILITY COMPANY REPRESENTATIVES SHALL BE ON SITE DURING TIMES OF EXCAVATION IN THE VICINITY OF THEIR FACILITIES. ANY DISCREPANCIES, OMISSIONS, AND/OR CONFLICTS TO BE ADDRESSED TO CONTRACTING OFFICER'S REPRESENTATIVE (COR) PRIOR TO CONTINUATION OF WORK.

3. ALL EXCAVATIONS SHALL BE BASED ON INFORMATION PROVIDED BY THE OWNER.

4. ALL EXCAVATION, WHETHER THEY ARE UTILITY TRENCHES OR FOOTING EXCAVATIONS, SHALL BE CONSTRUCTED IN ACCORDANCE WITH THE LATEST OCCUPATIONAL SAFETY AND HEALTH ADMINISTRATION (OSHA) "CONSTRUCTION STANDARDS FOR EXCAVATION."

5. PRIOR TO BEGINNING ANY WORK ON THE SITE, THE CONTRACTOR SHALL CONTACT THE COR FOR SPECIFIC INSTRUCTIONS RELEVANT TO THE SEQUENCING OF WORK.

6. REFERENCES LINES AND GRADES SHALL BE MAINTAINED DURING THE PROGRESS OF THE WORK.

7. THE CONTRACTOR SHALL RESTORE TO ORIGINAL CONDITION ALL "OFF SITE" PROPERTY AND EASEMENTS DISTURBED BY HIS OPERATIONS.

8. THE CONTRACTOR SHALL KEEP EXISTING ROADWAYS AND SIDEWALKS CLEAN OF MUD AND DEBRIS AT ALL TIMES.

9. ALL CUT AREAS AND AREAS TO RECEIVE FILL AND BACK FILL SHALL BE TOPSOILED TO TOPSOIL, SOFT SOIL, OR OTHER DELETERIOUS MATERIALS. STRIPPED SOIL TO BE STOCKPILED FOR LATER USE DURING LANDSCAPING OR BE REMOVED FROM SITE UPON COR WRITTEN APPROVAL.

10. SILTATION AND EROSION CONTROL DEVICES SHALL BE INSTALLED AS SPECIFIED IN THE ENVIRONMENTAL PROTECTION PLAN, PRIOR TO ANY GRADING OPERATIONS AND SHALL BE INSPECTED AND MAINTAINED ON A REGULAR BASIS UNTIL SUFFICIENT VEGETATION HAS BEEN ESTABLISHED ON THE SITE TO PREVENT EROSION.

11. CONTRACTOR SHALL VERIFY THE LOCATION OF THE EXISTING UTILITIES PRIOR TO ANY GRADING OPERATIONS AND PROTECT THE UTILITIES DURING THIS WORK.

12. SOD ALL DISTURBED AREAS NOT NOTED TO BE IMPROVED PER SECTION 010000.

13. CONTRACTOR TO PROVIDE SAMPLES AND MOCK-UPS OF ALL MATERIALS FOR COR APPROVAL. COLORS TO BE REVIEWED AND APPROVED BY COR. THIS SHOULD INCLUDE SAMPLES OF:

- ALL JOINTS, SEALANTS, AND COLORS
- CONCRETE PAVING
- PAVERS
- WALL MATERIALS
- PLANT MATERIAL
- BOLLARDS & MULCH.

14. CONTRACTOR TO PROVIDE 4' x 4' MOCK UP OF ALL MATERIALS AND PATTERNS FOR COR APPROVAL.

15. ALL EXTERIOR CONCRETE PAVING SHALL MEET BUILDING FINISH FLOOR ELEVATION, TYP.

16. GENERAL CONTRACTOR SHALL COORDINATE ALL WORK BETWEEN LANDSCAPING, CABINING, LANDSCAPE CONTRACTORS, AND OTHER TRADES

17. ALL MATERIAL TYPES, COLORS, FINISHES, AND PROCESSES SHALL BE SELECTED AND APPROVED BY COR.

18. ALL PAVING TO BE LAID OUT IN THE FIELD BY THE CONTRACTOR FOR APPROVAL BY THE COR AND LANDSCAPE ARCHITECT PRIOR TO ANY CONSTRUCTION

19. DO NOT DISTURB ANY UTILITIES UNLESS NOTED OTHERWISE.

20. USE OF EXPLOSIVES AND BURNING ON-SITE WILL NOT BE PERMITTED.

21. SIGNS, LIGHTS, AND BARRICADES SHALL BE INSTALLED AT LOCATIONS NECESSARY TO MAINTAIN A SAFE WORK SITE CONDITION AS DIRECTED AND APPROVED BY THE COR AND IN ACCORDANCE WITH THE MEANS FOR UNIFORM TRAFFIC CONTROL DEVICES

22. THE CONTRACTOR SHALL OBTAIN ALL NECESSARY PERMITS TO ACCOMPLISH THIS WORK. THE COST OF THESE PERMITS SHALL BE INCLUDED IN THE CONTRACT AMOUNT.

23. ALL QUESTIONS REGARDING THESE CONSTRUCTION DOCUMENTS SHALL BE SUBMITTED IN WRITING TO THE COR.


 Call Before you DIG
TOLL FREE
1-800-344-7483
MISSOURI ONE-CALL SYSTEM INC.
MODOT (314) 340-4100

 Department of
Veterans Affairs



- 4E

three inches = one foot
one and one half inches = one foot
one inch = one foot
three quarters inch = one foot
one half inch = one foot
three eighths inch = one foot
one quarter inch = one foot
one eighth inch = one foot
one sixteenth inch = one foot




- LEGEND**
- + TC 600.75 TOP OF CURB ELEVATION
 - + BC 600.25 BOTTOM OF CURB ELEVATION
 - + TW 600.75 TOP OF WALL ELEVATION
 - + BW 595.25 BOTTOM OF WALL ELEVATION
 - + 600.75 SPOT ELEVATION
 - 600 CONTOURS
 - EJ EXPANSION JOINTS
 - CJ CONTROL JOINT
 - PA PLANTING AREA
 - PERFORATED PIPE WITH FILTER SOCK. CONNECT TO STORM DRAIN PIPE. SEE CIVIL DRAWINGS.
 - 1 STANDARD CONCRETE PEDESTRIAN PAVING**
5" THICK CONCRETE PAVING, LIGHT BROOM FINISH, SAW CUT JOINTS. EDGES TO BE 1/4" TOOLED RADIUS. SEE CIVIL DRAWINGS FOR DETAILS AND LAYOUT. CONTRACTOR TO COORDINATE LOCATION OF ALL JOINTS WITH LANDSCAPE ARCHITECT.
 - 2 2' x 2' MODULAR CONCRETE PAVER**
BASIS OF DESIGN: UNILOCK UMBRIANO 24" x 24" DIMENSIONAL PAVER, COLOR SUMMER WHEAT. SUBMIT COLOR SAMPLE FOR COR APPROVAL. INSTALL PER DETAIL 4E/LS-102 AND MANUFACTURERS SPECIFICATIONS.
 - 5 SITE WALL**
1'-4" WIDE CONCRETE AND BRICK VENEER WALL WITH CAST STONE CAP. REFER TO STRUCTURAL AND ARCHITECTURAL DRAWINGS FOR DETAILS
 - 6 8' SECURITY FENCE**
BLACK WELDED WIRE PANEL FENCE.
 - 7 EGRESS STAIR**
SEE ARCHITECTURAL DRAWINGS.
 - 8 DOUBLE SECURITY GATE 8' TALL X 10' WIDE**
STYLE TO MATCH FENCING. SEE ARCHITECTURAL DRAWINGS AND SPECIFICATIONS FOR SECURITY DEVICE AND LATCHING REQUIREMENTS. PROVIDE EXIT DEVICES FOR EGRESS REQUIREMENTS.
 - 9 ALUMINUM PAVER EDGE RESTRAINT**
INSTALL PER MANUFACTURE SPECIFICATIONS. SUBMIT PRODUCT DATA FOR APPROVAL TO COR AND LANDSCAPE ARCHITECT.
 - 10 SECURITY BOLLARD**
SEE ARCHITECTURAL DRAWINGS.
 - 11 SITE FURNITURE (OFOI)**
OWNER FURNISHED, OWNER INSTALLED AFTER COMPLETION OF CONSTRUCTION. ITEMS INCLUDE, BUT ARE NOT LIMITED TO BENCHES, TABLES & CHAIRS, ASH URNS, TRASH/RECYCLING RECEPTACLES
 - 12 MINERAL MULCH**
2" THICK LAYER OF 1.5" TO 3" DIA. CLEAN MERAMEC LANDSCAPE STONE, OR EQUAL, WITH WEED BARRIER. SUBMIT STONE SAMPLE FOR APPROVAL TO COR AND LANDSCAPE ARCHITECT.
 - 13 SITE PLANTER WALLS**
1'-0" WIDE CONCRETE AND BRICK VENEER WALL WITH CAST STONE CAP. REFER TO STRUCTURAL AND ARCHITECTURAL DRAWINGS FOR DETAILS

- NOTES:
- BID ALTERNATE 9, LOW WALLS AND PLANTERS. SEE SHEET LS-103A FOR ADJUSTED PAVEMENT LAYOUT.
 - FOR ACCESSIBILITY SIGNS REFER TO CS-105.



NOTIFY CONTRACTING OFFICER'S REPRESENTATIVE (COR) IMMEDIATELY IN EVENT OF DISCREPANCIES, OMISSIONS, AND/OR CONFLICTS IN THE DRAWINGS OR SPECIFICATIONS. THE CONTRACTOR IS NOT AUTHORIZED TO SCALE THE DRAWINGS. ALL QUESTIONS IN REFERENCE TO CONTRACT DOCUMENTS SHALL BE IMMEDIATELY DIRECTED TO THE COR.
FOR GRADING, CONTOURS, AND DETAILS, REFER TO CIVIL SHEETS



CONSTRUCTION DOCUMENTS - FINAL BID PACKAGE


CONSULTANTS: 7722 Big Bend Blvd. St. Louis, MO 63119 T: 314-644-5700 F: 314-644-6398		ARCHITECT/ENGINEERS: CANNON DESIGN 1100 Clark Avenue St. Louis, Missouri 63102 T: 314.241.6250 F: 314.241.2570 <small>© Cannon Design 2013 All rights reserved. No part of this document may be reproduced or utilized in any form, without prior written authorization by The Cannon Corporation.</small>		Drawing Title ENTRY SITE PLAN Approved: Project Director	Project Title John J. Pershing VAMC Clinical & Urgent Care Addition Location Poplar Bluff Missouri	Project Number 657-351 <small>SWT DESIGN PROJECT NO. R1208-01</small> Building Number Drawing Number LS-103 <small>Dwg. 3 of 11</small>	Office of Construction and Facilities Management
Revisions:	Date			Date DECEMBER 14, 2015	Checked BR, TS	Drawn ZTS	



- TO 600.75
+ BC 600.25
- TOP OF CURB ELEVATION
BOTTOM OF CURB ELEVATION
- + TW 600.75
+ BW 595.25
- TOP OF WALL ELEVATION
BOTTOM OF WALL ELEVATION
- + 600.75
- SPOT ELEVATION
- CONTOURS
- EJ EXPANSION JOINTS
- CJ CONTROL JOINT
- PA PLANTING AREA
- PERFORATED PIPE WITH FILTER SOCK. CONNECT TO STORM DRAIN PIPE. SEE CIVIL DRAWINGS.
- 1** **STANDARD CONCRETE PEDESTRIAN PAVING**
5" THICK CONCRETE PAVING, LIGHT BROOM FINISH
SAW CUT JOINTS, EDGES TO BE 1" TOOLED RADIUS
SEE CIVIL DRAWINGS FOR DETAILS AND LAYOUT.
CONTRACTOR TO COORDINATE LOCATION OF ALL JOINTS WITH LANDSCAPE ARCHITECT.
- 2** **2' x 2' MODULAR CONCRETE PAVER**
BASIS OF DESIGN: UNILOCK UMBRIANO 24" x 24" DIMENSIONAL PAVER, COLOR SUMMER WHEAT.
SUBMIT COLOR SAMPLE FOR COR APPROVAL.
INSTALL PER DETAIL 4E/L5-102 AND MANUFACTURERS SPECIFICATIONS.
- 5** **SITE WALL**
1'-4" WIDE CONCRETE AND BRICK VENEER WALL
WITH CAST STONE CAP. REFER TO STRUCTURAL AND ARCHITECTURAL DRAWINGS FOR DETAILS
- 6** **8' SECURITY FENCE**
BLACK WELDED WIRE PANEL FENCE.
- 7** **EGRESS STAIR**
SEE ARCHITECTURAL DRAWINGS.
- 8** **DOUBLE SECURITY GATE 8' TALL X 10' WIDE**
STYLE TO MATCH FENCING. SEE ARCHITECTURAL DRAWINGS AND SPECIFICATIONS FOR SECURITY DEVICE AND LATCHING REQUIREMENTS. PROVIDE EIT DEVICES FOR EGRESS REQUIREMENTS.
- 9** **ALUMINUM PAVER EDGE RESTRAINT**
INSTALL PER MANUFACTURE SPECIFICATIONS.
SUBMIT PRODUCT DATA FOR APPROVAL TO COR AND LANDSCAPE ARCHITECT.
- 10** **SECURITY BOLLARD**
SEE ARCHITECTURAL DRAWINGS.
- 11** **SITE FURNITURE (OFO)**
OWNER FURNISHED. OWNER INSTALLED AFTER COMPLETION OF CONSTRUCTION.
ITEMS INCLUDE, BUT ARE NOT LIMITED TO BENCHES, TABLES & CHAIRS, ASH URNS, TRASH/RECYCLING RECEPTACLES
- 12** **MINERAL MULCH**
2" THICK LAYER OF 1.5" TO 3" DIA. CLEAN MERRAMEC LANDSCAPE STONE, OR EQUAL, WITH WEED BARRIER. SUBMIT STONE SAMPLE FOR APPROVAL TO COR AND LANDSCAPE ARCHITECT.
- 13** **SITE PLANTER WALLS**
1'-0" WIDE CONCRETE AND BRICK VENEER WALL WITH CAST STONE CAP. REFER TO STRUCTURAL AND ARCHITECTURAL DRAWINGS FOR DETAILS

CONSTRUCTION DOCUMENTS - FINAL BID PACKAGE

three inches = one foot
one and one half inches = one foot
one inch = one foot
three quarters inch = one foot
one half inch = one foot
three eighths inch = one foot
one quarter inch = one foot
one eighth inch = one foot
one sixteenth inch = one foot



LEGEND

A CANOPY TREES

B EVERGREEN TREES

C ORNAMENTAL TREES

SHRUBS

GROUNDCOVER / PERENNIALS

TP TREE PROTECTION FENCE

11" MIN.
TREE PRESERVATION AREA
19" MIN.
MACHINERY ACCESS, DUMPING OR STORAGE OF MATERIALS IS PROHIBITED. FINES WILL BE ASSESSED TO ANY TREES DAMAGED WITHIN FENCE
ATTACH TO TOP OF TREE PROTECTION FENCE POST


NOTES:
1) TYPE SIZE SHOULD BE NO SMALLER THAN 48 PT. (1/2" HT.)
2) SIMILAR SIGNS REQUESTING SUBCONTRACTOR COOPERATION AND COMPLIANCE WITH TREE PROTECTION STANDARDS ARE RECOMMENDED AT THE SITE ENTRANCE.
3) SIGNS SHOULD BE PLACED AT A DISTANCE NOT TO EXCEED 50'.

A8 TREE PROTECTION SIGN
N.T.S.

PLANT SCHEDULE		
DECIDUOUS TREES	BOTANICAL NAME	COMMON NAME
A1	Gleditsia triacanthos inermis 'Shademaster' TM	'Shademaster' Honey Locust
FLOWERING TREES	BOTANICAL NAME	COMMON NAME
C1	Amelanchier x grandiflora 'Autumn Brilliance'	'Autumn Brilliance' Serviceberry
C2	Cercis canadensis 'Appalachian Red'	'Appalachian Red' Redbud
SHRUBS	BOTANICAL NAME	COMMON NAME

TREE PROTECTION & PRESERVATION NOTES:

- A PRE-CONSTRUCTION MEETING WILL BE HELD ON SITE. DURING THIS MEETING TREE PROTECTION MEASURES WILL BE DISTRIBUTED TO OPERATORS, CONSTRUCTION SUPERVISORS, AND C.O.R.
- CLEARING LIMITS SHALL BE ROUGH STAKED BY CONTRACTOR IN ORDER TO FACILITATE LOCATION FOR TRENCHING AND FENCING INSTALLATION.
- NO CLEARING OR GRADING SHALL BEGIN IN AREAS WHERE TREE TREATMENT AND PRESERVATION MEASURES HAVE NOT BEEN COMPLETED.
- THE SEQUENCE OF TREE TREATMENT AND PRESERVATION MEASURES SHALL BE:
 - ROOT PRUNING TRENCHING WHERE EXCAVATION WILL OCCUR WITHIN TREE'S DRIP LINE.
 - TREE PROTECTION FENCING
 - TREE PRUNING AS DIRECTED BY C.O.R. TO REMOVE BRANCHES IN CONFLICT WITH WORK TO BE PERFORMED.
 - SIGN INSTALLATION
- ALL TREATMENT AND PRESERVATION MEASURES SHALL BE DIRECTED IN THE FIELD BY THE C.O.R.
- TREE PROTECTION FENCING SHALL BE MAINTAINED AND REPAIRED BY THE CONTRACTOR FOR THE DURATION OF CONSTRUCTION. ONCE APPROVED BY THE C.O.R., THE FENCE SHALL NOT BE ALTERED WITHOUT PRIOR APPROVAL BY THE C.O.R.
- ACCESS TO FENCED AREAS BY EQUIPMENT, MATERIALS, OR INDIVIDUALS THAT MAY CAUSE HARM TO THE PROTECTED TREES WILL ONLY BE PERMITTED WITH THE PRIOR APPROVAL OF THE C.O.R.
- TREES, SHRUBS, OR UNDERGROWTH SHALL BE REMOVED FROM PROTECTED AREAS ONLY WHEN NECESSARY AND SHALL BE PERFORMED WITH HAND TOOLS ONLY.
- ATTACHMENT OF SIGNAGE, FENCING, ETC. TO ANY TREE TO BE SAVED IS PROHIBITED.
- AFTER CONSTRUCTION, ALL TEMPORARY BARRIERS, FENCING, DEBRIS, ETC. SHALL BE REMOVED FROM THE SITE BY THE CONTRACTOR.



E8 TYPICAL TREE PROTECTION
N.T.S.

1F TREE PLANTING PLAN
SCALE: 1" = 20'

Call Before you DIG
TOLL FREE
1-800-344-7483
MISSOURI ONE-CALL SYSTEM INC.
MODOT (314) 340-4100

NOTIFY CONTRACTING OFFICER'S REPRESENTATIVE (COR) IMMEDIATELY IN EVENTS OF DISCREPANCIES, OMISSIONS, AND/OR CONFLICTS IN THE DRAWINGS OR SPECIFICATIONS. THE CONTRACTOR IS NOT AUTHORIZED TO SCALE THE DRAWINGS. ALL QUESTIONS IN REFERENCE TO CONTRACT DOCUMENTS SHALL BE IMMEDIATELY DIRECTED TO THE COR.

FOR LANDSCAPE CONSTRUCTION DETAILS AND NOTES, REFER TO SHEET LD-501
FOR LANDSCAPE PLANTING SCHEDULE, REFER TO SHEET LD-501
FOR GRADING, CONTOURS, AND DETAILS, REFER TO CIVIL SHEETS

CONSULTANTS:



7722 Big Bend Blvd.
St. Louis, MO 63119
T: 314-644-5700
F: 314-644-6398

ARCHITECT/ENGINEERS:

CANNONDESIGN

1100 Clark Avenue
St. Louis, Missouri 63102
T: 314.241.6250
F: 314.241.2570

© Cannon Design 2013
All rights reserved. No part of this document may be reproduced or utilized in any form, without prior written authorization by The Cannon Corporation.

Drawing Title
TREE PLANTING PLAN

Approved: Project Director

Project Title
**John J. Pershing VAMC
Clinical & Urgent Care Addition**

Location
Poplar Bluff Missouri

Date
DECEMBER 14, 2015

Checked
BR, TS

Drawn
ZTS

Project Number
657-351
SWT DESIGN PROJECT NO. R1208.011
Building Number

Drawing Number
LP-101

Dwg. 6 of 11

CONSTRUCTION DOCUMENTS - FINAL BID PACKAGE

Office of
Construction
and Facilities
Management



CANOPY TREES

EVERGREEN TREES

ORNAMENTAL TREES

SHRUBS

GROUNDCOVER / PERENNIALS




NOTIFY CONTRACTING OFFICER'S REPRESENTATIVE (COR) IMMEDIATELY IN
EVENTS OF DISCREPANCIES, OMISSIONS, AND/OR CONFLICTS IN THE
DRAWINGS OR SPECIFICATIONS. THE CONTRACTOR IS NOT AUTHORIZED TO
SCALE THE DRAWINGS. ALL QUESTIONS IN REFERENCE TO CONTRACT
DOCUMENTS SHALL BE IMMEDIATELY DIRECTED TO THE COR.

 Call Before you DIG
TOLL FREE
1-800-344-7483
MISSOURI ONE-CALL SYSTEM INC.


CONSTRUCTION DOCUMENTS - FINAL BID PACKAGE

 Department of
Veterans AffairsVA FORM 08-6231

three inches = one foot
one and one half inches = one foot
one inch = one foot
three quarters inch = one foot
one half inch = one foot
three eighths inch = one foot
one quarter inch = one foot
one eighth inch = one foot
one sixteenth inch = one foot



1D UNDERSTORY PLANTING PLAN
1" = 10'



LEGEND

- CANOPY TREES
- EVERGREEN TREES
- ORNAMENTAL TREES
- SHRUBS
- GROUNDCOVER / PERENNIALS

PLANT SCHEDULE

SHRUBS	BOTANICAL NAME	COMMON NAME
BG	Buxus x 'Green Gem'	'Green Gem' Boxwood
IJ	Ilex verticillata 'Jim Dandy'	'Jim Dandy' Winterberry
IR	Ilex verticillata 'Red Sprite'	'Red Sprite' Winterberry
ORNAMENTAL GRASSES	BOTANICAL NAME	COMMON NAME
BB	Bouteloua gracilis 'Blonde Ambition'	'Blonde Ambition' Blue Grama
CI	Carex x 'Ice Dance'	'Ice Dance' Sedge
SH	Sporobolus heterolepis	Prairie Dropseed
PERENNIALS	BOTANICAL NAME	COMMON NAME
AG	Allium giganteum	Giant Allium
AP	Aster novae-angliae 'Purple Dome'	'Purple Dome' New England Aster
LK	Liatris spicata 'Kobold'	'Kobold' Gayfeather
RS	Rudbeckia fulgida sullivantii 'Little Goldstar'	'Little Goldstar' Black-eyed Susans

Call Before you DIG
TOLL FREE
1-800-344-7483
MISSOURI ONE-CALL SYSTEM INC.
MODOT (314) 340-4100

NOTIFY CONTRACTING OFFICER'S REPRESENTATIVE (COR) IMMEDIATELY IN EVENTS OF DISCREPANCIES, OMISSIONS, AND/OR CONFLICTS IN THE DRAWINGS OR SPECIFICATIONS. THE CONTRACTOR IS NOT AUTHORIZED TO SCALE THE DRAWINGS. ALL QUESTIONS IN REFERENCE TO CONTRACT DOCUMENTS SHALL BE IMMEDIATELY DIRECTED TO THE COR.

FOR LANDSCAPE CONSTRUCTION DETAILS AND NOTES, REFER TO SHEET LD-501
FOR LANDSCAPE PLANTING SCHEDULE, REFER TO SHEET LD-501
FOR GRADING, CONTOURS, AND DETAILS, REFER TO CIVIL SHEETS

NOTES:
DEDUCT ALTERNATE #9 LOW WALLS AND PLANTERS.
SEE SHEET LP-104A FOR ALTERNATE PLANTING PLAN.

CONSULTANTS:



7722 Big Bend Blvd.
St. Louis, MO 63119
T: 314-644-5700
F: 314-644-6378

ARCHITECT/ENGINEERS:

CANNON DESIGN


1100 Clark Avenue
St. Louis, Missouri 63102
T: 314.241.6250
F: 314.241.2570

© Cannon Design 2013
All rights reserved. No part of this document may be reproduced or utilized in any form, without prior written authorization by The Cannon Corporation.

CONSTRUCTION DOCUMENTS - FINAL BID PACKAGE

Drawing Title AMBULANCE BAY UNDERSTORY PLANTING PLAN	Project Title John J. Pershing VAMC Clinical & Urgent Care Addition	Project Number 657-351 SWT DESIGN PROJECT NO. R12086.01	Office of Construction and Facilities Management Department of Veterans Affairs
Approved: Project Director	Location Poplar Bluff Missouri	Building Number	
Date DECEMBER 14, 2015	Checked BR, TS	Drawn ZTS	Drawing Number LP-103 Dwg. 8 of 11

Three inches = one foot
One and one half inches = one foot
One inch = one foot
Three quarters inch = one foot
One half inch = one foot
Three eighths inch = one foot
One quarter inch = one foot
One eighth inch = one foot
One sixteenth inch = one foot




LEGEND

- CANOPY TREES
- EVERGREEN TREES
- ORNAMENTAL TREES
- SHRUBS
- GROUNDCOVER / PERENNIALS

PLANT SCHEDULE					
SOD	QTY	BOTANICAL NAME	COMMON NAME	TYPE	COMMENTS
	35,375 sf	Festuca spp. Fescue Mix	Turf-type Tall Fescue	Sod	Per Specifications: 3 Improved Cultivars, Min.

1F TURF SOD PLAN
1" = 20'



Call Before you DIG
TOLL FREE
1-800-344-7483
MISSOURI ONE-CALL SYSTEM INC.
MODOT (314) 340-4100

NOTIFY CONTRACTING OFFICER'S REPRESENTATIVE (COR) IMMEDIATELY IN EVENTS OF DISCREPANCIES, OMISSIONS, AND/OR CONFLICTS IN THE DRAWINGS OR SPECIFICATIONS. THE CONTRACTOR IS NOT AUTHORIZED TO SCALE THE DRAWINGS. ALL QUESTIONS IN REFERENCE TO CONTRACT DOCUMENTS SHALL BE IMMEDIATELY DIRECTED TO THE COR.

FOR LANDSCAPE CONSTRUCTION DETAILS AND NOTES, REFER TO SHEET LD-501
FOR LANDSCAPE PLANTING SCHEDULE, REFER TO SHEET LD-501
FOR GRADING, CONTOURS, AND DETAILS, REFER TO CIVIL SHEETS

CONSULTANTS:

SWT DESIGN

7722 Big Bend Blvd.
St. Louis, Mo 63119
t. 314-644-5700
f. 314-644-6378

ARCHITECT/ENGINEERS:

CANNON DESIGN

1100 Clark Avenue
St. Louis, Missouri 63102
T: 314.241.6250
F: 314.241.2570

© Cannon Design 2013
All rights reserved. No part of this document may be reproduced or utilized in any form, without prior written authorization by The Cannon Corporation.

Drawing Title

SEED & SOD PLAN

Approved: Project Director

Project Title

**John J. Pershing VAMC
Clinical & Urgent Care Addition**

Location

Poplar Bluff Missouri

Date

DECEMBER 14, 2015

Checked

BR, TS

Drawn

ZTS

Project Number

657-351

Building Number

SWT DESIGN PROJECT NO. R12086.01

Drawing Number


LP-104

Dwg. 9 of 11

Office of
Construction
and Facilities
Management

Department of
Veterans Affairs

three inches = one foot
one and one half inches = one foot
one inch = one foot
three quarters inch = one foot
one half inch = one foot
three eighths inch = one foot
one quarter inch = one foot
one eighth inch = one foot
one sixteenth inch = one foot




1F BID ALTERNATE 9 - PLANTING PLAN
1" = 20'

LEGEND

- SHRUBS
- GROUND COVER / PERENNIALS
- SEED

ALTERNATE #9 PLANT SCHEDULE						
ORNAMENTAL GRASSES	QTY	BOTANICAL NAME	COMMON NAME	SPACING	SIZE	COMMENTS
CI	16	Carex x 'Ice Dance'	'Ice Dance' Sedge	18" O.C.	#1	Per Details, Cont.
SH	226	Sporobolus heterolepis	Prairie Dropseed	24" O.C.	#1	Per Details, Cont.
PERENNIALS	QTY	BOTANICAL NAME	COMMON NAME	SPACING	SIZE	COMMENTS
AG	16	Allium giganteum	Giant Allium	18" O.C.	12 cm min	Interplanted in ornamental grass at circle
LK	101	Liatis spicata 'Kobold'	'Kobold' Gayfeather	36" O.C.	#1	Per Details, Cont.
TURF SEED	QTY	BOTANICAL NAME	COMMON NAME	TYPE	-	COMMENTS
	24,770 sf	Festuca spp. Fescue Mix	Turf-type Tall Fescue	Seed		Per Specifications; 3 Improved Cultivars, Min.



Call Before you DIG
TOLL FREE
1-800-344-7483
MISSOURI ONE-CALL SYSTEM INC.
MODOT (314) 340-4100

NOTIFY CONTRACTING OFFICER'S REPRESENTATIVE (COR) IMMEDIATELY IN EVENTS OF DISCREPANCIES, OMISSIONS, AND/OR CONFLICTS IN THE DRAWINGS OR SPECIFICATIONS. THE CONTRACTOR IS NOT AUTHORIZED TO SCALE THE DRAWINGS. ALL QUESTIONS IN REFERENCE TO CONTRACT DOCUMENTS SHALL BE IMMEDIATELY DIRECTED TO THE COR.

FOR LANDSCAPE CONSTRUCTION DETAILS AND NOTES, REFER TO SHEET LD-501
FOR LANDSCAPE PLANTING SCHEDULE, REFER TO SHEET LD-501
FOR GRADING, CONTOURS, AND DETAILS, REFER TO CIVIL SHEETS

CONSULTANTS:



7722 Big Bend Blvd.
St. Louis, MO 63119
T: 314-644-5700
F: 314-644-5958

ARCHITECT/ENGINEERS:

CANNON DESIGN

1100 Clark Avenue
St. Louis, Missouri 63102
T: 314.241.6250
F: 314.241.2570

© Cannon Design 2013
All rights reserved. No part of this document may be reproduced or utilized in any form, without prior written authorization by The Cannon Corporation.

Drawing Title
**BID ALTERNATE 9
PLANTING PLAN**

Approved: Project Director

Project Title
**John J. Pershing VAMC
Clinical & Urgent Care Addition**

Location
Poplar Bluff Missouri

Date
DECEMBER 14, 2015

Checked
BR, TS


Drawn
ZTS

Project Number
657-351
SWT DESIGN PROJECT NO. R12086.01
Building Number
Drawing Number
LP-104A
Dwg. 10 of 11

Office of
Construction
and Facilities
Management



1. CONTRACTOR SHALL COMPLY WITH ALL FEDERAL, STATE AND LOCAL LAWS AND REGULATIONS PERTAINING TO THE INSPECTION FOR PLANT DISEASE AND INSECT INFESTATION.
2. LANDSCAPE ARCHITECT SHALL APPROVE ALL PLANT MATERIAL AND PLACEMENT PRIOR TO INSTALLATION. CONTACT LANDSCAPE ARCHITECT AT LEAST TWO (2) WEEKS PRIOR TO REVIEW.
3. ALL TREES AND SHRUBS SHALL EQUAL OR SURPASS AMERICAN STANDARDS FOR NURSERY STOCK ANSI Z60.1, 2004 FOR SIZE AND QUALITY.
4. CONTRACTOR SHALL VERIFY THE PLANT MATERIAL IS PROPERLY LABELED, IS OF PROPER SIZE, HAS A WELL DEVELOPED BRANCH AND ROOT STRUCTURE, AND IS IN ACCORDANCE WITH THE AMERICAN ASSOCIATION OF NURSERYMEN. COMPLY WITH THE FOLLOWING:
 - A. DO NOT PRUNE PLANT MATERIAL PRIOR TO DELIVERY WITHOUT SPECIFIC APPROVAL BY LANDSCAPE ARCHITECT.
 - B. PLANTS ARE SUBJECT TO LANDSCAPE ARCHITECT INSPECTION FOR SIZE, VARIETY, CONDITION, LATENT DEFECTS, AND INJURY AT THE PLACE OF GROWTH AND AT THE PROJECT SITE AT ANY TIME BEFORE AND DURING PROGRESS OF WORK.
 - C. WHEN REQUESTED BY LANDSCAPE ARCHITECT, SHOW SAMPLES TO PROVE THAT NO ROOT BOUND CONDITIONS EXIST.
 - D. REMOVE REJECTED PLANTS FROM THE SITE IMMEDIATELY AND REPLACE WITH LANDSCAPE ARCHITECT APPROVED MATERIALS.
 - E. REPLACEMENT PLANTS SHALL BE THE SAME TYPE AND SIZE AS ORIGINALLY PLANTED.
5. SUBSTITUTIONS SHALL NOT BE PERMITTED WITHOUT THE LANDSCAPE ARCHITECT'S WRITTEN APPROVAL.
6. CONTRACTOR SHALL PROVIDE A WRITTEN GUARANTEE TO THE OWNER THAT ALL TREES, SHRUBS, AND PLANT MATERIALS WILL MAINTAIN VIGOROUS AND HEALTHY GROWTH FOR THE SPECIFIED GUARANTEE PERIOD OF ONE YEAR, UNLESS OTHERWISE STATED.
7. GUARANTEE PERIOD SHALL BEGIN ON THE DATE OF FINAL WRITTEN ACCEPTANCE OF WORK BY THE COR, AFTER SUCCESSFUL COMPLETION OF THE SPECIFIED MAINTENANCE PERIOD.
8. CONTRACTOR SHALL REMOVE TAGS, LABELS, NURSERY STAKES, WIRE BASKETS OR CAGES, AND TIES FROM ALL PLANTS.
9. SOIL PREPARATION, FERTILIZATION, PLANTING, AND STAKING AND GUYING SHALL CONFORM TO DETAILS AND SPECIFICATIONS.
10. PLANT MATERIAL QUANTITIES ARE PROVIDED FOR PRELIMINARY COST ESTIMATE PURPOSES ONLY. LANDSCAPE CONTRACTOR IS RESPONSIBLE FOR VERIFYING QUANTITIES AS SHOWN ON PLANS.
11. CONTRACTOR SHALL COORDINATE LOCATION OF PLANT MATERIAL WITH ALL OTHER CONTRACTORS.
12. ALL PLANT PIT EXCAVATION SHALL BE PER DETAILS AND SPECIFICATIONS.
13. IF PLANTING PITS ARE EXCAVATED USING A POWER AUGER, BREAK VERTICAL SIDES WITH A BALLING BAR OR SPADE TO INTERRUPT CONTINUOUS CURVE INFLUENCE ON ROOT DEVELOPMENT.
14. ALL SOIL FOR LANDSCAPE PLANTING AREAS OR BERMS SHALL BE OBTAINED FROM OFF-SITE EXCAVATIONS AND CONTRACTOR SHALL INDICATE SOURCE LOCATION. SOILS SHALL BE SANDY LOAM CONTAINING NO TOXIC CHEMICALS OR ELEMENTS WHICH MAY INHIBIT OR RETARD NORMAL PLANT GROWTH. CONTRACTOR SHALL PROVIDE A SOIL SUITABILITY TEST TO DETERMINE SOIL FERTILITY. THE RESULTS OF THIS SOIL STUDY SHALL SERVE AS THE RECOMMENDATIONS FOR ANY NECESSARY SOIL AMENDMENTS. SOIL SURVEY RESULTS SHALL BE PROVIDED TO THE LANDSCAPE ARCHITECT FOR APPROVAL PRIOR TO SOIL PLACEMENT. ALL SOIL AMENDMENTS SHALL CONFORM TO INDUSTRY STANDARDS.
15. CONTRACTOR SHALL KILL AND REMOVE ALL EXISTING WEEDS FROM SITE.
16. SOIL PREPARATION AND BACKFILL RECOMMENDATIONS CONTAINED WITHIN THESE PLANS AND/OR SPECIFICATIONS ARE FOR BID PURPOSES ONLY. FINAL SOIL ANALYSIS RECOMMENDATIONS SHALL SUPERSEDE. SEE SPECIFICATIONS.
17. CONTRACTOR SHALL REMOVE A MINIMUM OF ONE SOIL SAMPLE FOR TESTING FROM EACH PLANTING AREA AS SHOWN ON PLAN. A COPY OF THE SOILS REPORT WITH RECOMMENDATIONS SHALL BE GIVEN TO THE OWNER AND THE LANDSCAPE ARCHITECT PRIOR TO ANY WORK BEING DONE. THE CONTRACTOR SHALL NOTIFY THE LANDSCAPE ARCHITECT OF ANY SOIL PROBLEMS THAT MIGHT AFFECT PLANT GROWTH.
18. CONTRACTOR SHALL INSTALL AMENDED SOIL MIX PER SOIL ANALYSIS RECOMMENDATIONS AND AS APPROVED BY LANDSCAPE ARCHITECT. SCARIFY SUBSOIL, INSTALL AND INCORPORATE AMENDED TOPSOIL AS PER SPECIFICATIONS, IN ALL PLANTING AND LAWN AREAS.
19. AMENDED SOIL MIX TO BE INSTALLED UP TO 2" BELOW FINISH GRADE ADJACENT TO PAVEMENT AND BUILDING STRUCTURES AT PLANTING AREAS TO ALLOW FOR MULCH; AND 2" BELOW FINISH GRADE ADJACENT TO BUILDING STRUCTURES AND PAVEMENT AT TURF AREAS.
20. BERMS AND SLOPES ADJACENT TO PAVEMENT TO BE GRADED PER DETAILS.
21. CONTRACTOR SHALL REMOVE ALL EXCESS SOIL, CONTAMINATED SOILS, ROCKS, CLOUDS, AND DEBRIS AS IT ACCUMULATES ON A DAILY BASIS.
22. CONTRACTOR SHALL GRADE AROUND ALL PLANTS TO FINISH GRADE UNLESS OTHERWISE NOTED.
23. ALL LANDSCAPE AREAS (EXCLUDING TURF) ARE TO BE MULCHED WITH A 2" DEEP LAYER OF BARK MULCH AT THE CONCLUSION OF PLANTING OPERATIONS. MULCH SHALL BE DOUBLE GROUND, WELL DECOMPOSED BARK MULCH, 1" DIAMETER IN SIZE OR SMALLER.
24. ALL TRANSITIONS BETWEEN PLANTING BEDS AND LAWNS ARE TO BE SPADE CUT EDGE, UNLESS OTHERWISE NOTED.
25. ALL PLANTINGS, EXCLUDING SEED AND SOD, SHALL BE HELD 3' CLEAR OF FIRE HYDRANTS.
26. ALL PLANTING AREAS WITHIN CONCRETE PAVING TO BE LAID OUT IN THE FIELD BY THE CONTRACTOR FOR APPROVAL BY LANDSCAPE ARCHITECT PRIOR TO ANY CONSTRUCTION.
27. THE LANDSCAPE CONTRACTOR TO COORDINATE INSTALLATION OF ALL LIGHTING EQUIPMENT PER THE LIGHTING SHEET AND PER DIRECTIONS AND APPROVAL OF THE LANDSCAPE ARCHITECT IN THE FIELD. SEE ELECTRICAL PLANS FOR INFORMATION ON WIRING, TYPICAL.



SEE PLANS

WALL AND CAP PER ARCHITECT'S PLANS AND DETAILS.

EXPANSION JOINT PER CIVIL PLANS AND DETAILS.

PAVEMENT AND BASE PER CIVIL PLANS AND DETAILS



FOOTINGS PER ARCHITECTURE AND STRUCTURAL DETAILS.

PERFORATED PIPE WITH FILTER SOCK CONNECTED TO STORM SYSTEM. SEE CIVIL DRAWINGS. TYP.

6" CLEAN AGGREGATE

FILTER FABRIC

7C SECTION A - BOX PLANTER
N.T.S.



FOR LANDSCAPE CONSTRUCTION DETAILS AND NOTES, REFER TO SHEET LD-501
FOR LANDSCAPE PLANTING SCHEDULE, REFER TO SHEET LD-501
FOR GRADING, CONTOURS, AND DETAILS, REFER TO CIVIL SHEETS

NOTIFY CONTRACTING OFFICER'S REPRESENTATIVE (COR) IMMEDIATELY IN EVENTS OF DISCREPANCIES, OMISSIONS, AND/OR CONFLICTS IN THE DRAWINGS OR SPECIFICATIONS. THE CONTRACTOR IS NOT AUTHORIZED TO SCALE THE DRAWINGS. ALL QUESTIONS IN REFERENCE TO CONTRACT DOCUMENTS SHALL BE IMMEDIATELY DIRECTED TO THE COR.

[illegible]

7722 Big Bend Blvd
St. Louis, MO 63119
t. 314-644-5700
f. 314-644-6378

CANNONDESIGN

1100 Clark Avenue
St. Louis, Missouri 63102
T: 314.241.6250
F: 314.241.2570

© Canon Design 2013
All rights reserved. No part of this document may be reproduced or utilized in any form, without prior written authorization by The Canon Corporation.

Drawing Title <div>PLANTING DETAILS</div>		Project Title <div>John J. Pershing VAMC Clinical & Urgent Care Addition</div>		Project Number <div>657-351</div> <small>SMT DESIGN/PROJECT NO. 011308-01</small>		<div>Office of Construction and Facilities Management</div>
Approved: Project Director		Location <div>Poplar Bluff Missouri</div>		Building Number <div>LD-501</div> <small>Dwg. 11 of 11</small>		
		Date <div>DECEMBER 14, 2015</div>	Checked <div>BR, TS</div>	Drawn <div>ZTS</div>		

Office of
Construction
and Facilities
Management

